LOCAL OFFICIALS BRIEFING

Prince Rodgers Ave, Bridges over Rt 287

Township of Bridgewater, Somerset County, NJ

Structures 1813-161 and 1813-162 MP 16.92 along Rt 287





AGENDA

- Welcome/Introductions
- Project Background
- Existing Conditions
- Proposed Construction
- Detours
- Next Steps
- Open Discussion/Questions



PROJECT TEAM

NJDOT PM: Pruthvi Patel

NJDOT APM: Jae-Yoon Jin

NJDOT Project Coordinator/

Lead Designer: Rongdu Lu

NJDOT Structural Engineers: Andrew Branin &

Michael Wilcox



PROJECT LOCATION MAP



PROJECT GOAL

Replace the Deck to improve the structurally deficient condition and ensure long term safety for all users.

Repair Superstructure and Substructure to address existing deterioration and extend the service life of the bridge.

Relocation of bridge mounted Sign Structure

Minimize impacts to Social, Economic and Environmental resource

PROJECT STATUS

New Jersey Department of Transportation Capital Project Delivery Process Current Phase **Overview Diagram**



Key Tasks

Problem Screening

Planning Funds

Review Problem Statement Subject Matter Expert Review Check NJDOT Management Systems Prioritize Problem Statements Validate Problem CPC Approval and Assignment

Obtain Public nput

Problem Statement Validation Problem Screening Report Proposed Project Assignment (CPM) or Maintenance/Operations)

Division of Capital Investment and Program Coordination & Division of **Project Management**

Concept Development

Planning Funds

Conduct Data Collection

Evaluate Deficiencies and Identify Fatal Flaws

Evaluate Planning Alternatives Coordinate with Stakeholders

Complete Environmental Screening Assess Right of Way (ROW) and Access Impacts

Determine Preliminary Preferred Alternative (PPA)

Identify Substandard Design

Determine Environmental Document Prepare Construction Cost Estimate Select Designer

Execute Public Involvement Action Plan

Design Communications Report Concept Development Report:

Purpose and Need Statement Preliminary Preferred Alternative **Environmental Document**

Classification **Preliminary Engineering Scope** Statement

Division of Project Management

Preliminary Engineering

Preliminary Engineering Authorization

Coordinate with Stakeholders

Conduct Environmental Analysis for PPA

Initiate Roadway Engineering

Initiate Structural Engineering

Initiate ROW and Access

Initiate Utility Engineering

Prepare Final Design and Construction Cost Estimates

Manage Project Contracts

Execute Public Involvement Action Plan

Design Communications Report Preliminary Engineering Report: Approved Environmental

Document Programment Approved Design Exception Report

Cost Estimates (Final Design & (construction) Approved Project Plan

Final Design Scope Statement

Division of Project Management

Final Design

Final Design Authorization ROW/Utility Authorizations

Manage Project Communications Complete Roadway Engineering Complete Structural Engineering Complete ROW and Access Complete Utility Engineering

Complete Environmental Process Prepare Final Design Submission Certify Construction Contract

Documents Manage Project Contracts

Execute Public Involvement Action Plan

Design Communications Report Environmental Reevaluations and Permits

Access Permits Acquisition of ROW Construction Contract Documents Supporting Agreements

Division of Project Management

Construction

Construction Authorization

Advertise for Bids

Award Project

Conduct Construction Startup

Conduct Mobilization

Manage Construction Changes

Conduct Construction Operations

Complete Construction

Closeout Project

Keep Public Informed

Maintain Community Support

Design Communications Report

Completed Project

As-Builts

Closeout Documentation

Division of Project Management and Division of Construction Services and Materials or Operations

PAST MEETINGS

- Concept Development Local Official Meeting January 2018
 - Township suggested closing both bridges entirely during construction and implementing a full detour.
 - Township recommended Garretson Road/Woodlawn Ave for the detour.
- Final Design Local Official Meeting April 2025
 - Detour and Staging plans were presented.
 - Township recommended In-Person PIC.

EXISTING CONDITIONS


- Structure No 1813-161 and 1813-162.
- 15' lanes one in each direction.
- 6' sidewalk on both sides.





- Out-to-out width of the bridges are 44'-6", with a curb-to-curb width of 30'.
- A curved-top chain link fence is mounted on top of concrete bridge parapets.

EXISTING CONDITIONS



- Bridges were built in 1963.
- The overall length of each bridge is 115'.
- They are separated by the I-287 median, a distance of 68'.

PROPOSED CONSTRUCTION


- Deck Replacements for both structures.
- Super-Structure and Sub-Structure repairs.
- Raising Profile by 2" along the structures.
- Removal of old exit sign attached to Structure 1813-161.
- Adding Two Overhead Sign Structures along Rt 287 NB.
- Adding Guide Rail along Rt 287.



PREFERRED STAGING

ONE STAGE CONSTRUCTION

- Construction method: Cast –in –Place.
- Vehicular and Pedestrian Detour during construction.
- Anticipated Construction time 13 months.




PROPOSED SECTION

ALTERNATE STAGING

TWO STAGE CONSTRUCTION


- Construction method: Cast –in –Place.
- Vehicular Detour during construction.
- No Pedestrian Detour during construction.
- Anticipated Construction time 18 months.





- Existing Electrical Pole will be relocated to be placed behind the Guide Rail.
- Existing PSE&G Live Gas Main will be relocated.
- Additional utility within the project limits:
 - Township of Bridgewater Sewer Utility.

EXISTING ELECTRICAL POLE



EXISTING GAS MAIN



EXISTING SIGN ATTACHED TO STRUCTURE 1813-161




APPROXIMATE LOCATION OF OHSS




PROPOSED OVERHEAD SIGN STRUCTURE LOCATIONS

0.75 MILES AND 1.5 MILES FROM RT. 78 FAST FXIT ALONG RT 287 NR



OHSS AT 1.5 MILES FROM RT. 78 EAST EXIT



OHSS AT 0.75 MILES FROM RT. 78 EAST EXIT

DETOURS

- Vehicular traffic will be detoured through North Bridge Street and through Woodlawn Avenue.
- AADT 5,726 vpd
- Projected 2040 AADT 7,036 vpd
- Pedestrian traffic can be detoured via North bridge Street.
- With preferred one stage construction the anticipated Vehicular and Pedestrian Detour :13 months
- With alternate two stage construction (No Pedestrian Detours), the anticipated Vehicular detour:18 months



VEHICLE DETOUR THROUGH NORTH BRIDGE STREET




VEHICLE DETOUR THROUGH WOODLAWN AVENUE





PEDESTRIAN DETOUR THROUGH NORTH BRIDGE STREET



PEDESTRIAN DETOUR THROUGH NORTH BRIDGE STREET

PEDESTRAIN DETOUR BENEFITS

Safety:

Pedestrians and bicyclists would be kept further away from the work zone, further reducing the chances of accidents or interference.

Long-Term Performance:

Fewer construction joints exposed to weather, road salt, etc. may improve the long-term performance of the new bridge components.

Control of Work:

Single stage construction would simplify inspection requirements during construction and would result in fewer traffic disruptions resulting from staged construction

PROJECT SCHEDULE


- Utility Coordination Underway
- Final Design Coordination under way
- Anticipated Construction Award Winter 2026-27
- Anticipated Vehicular and Pedestrian Detour: 13 months
- Anticipated Vehicular detour with Alternate Staging (No Pedestrian Detour): 18 months



NEXT STEPS

- Final Plans will be sent to the NJDOT SMEs and Local Officials for review Early Fall 2026.
- Project Support Letter for Detour Plans will be needed from Bridgewater Township.
- Meeting Minutes will be circulated.
- In-Person Pre-CON PIC (Public Information Center) will be scheduled.





CONTACT US:

Patience Sengbey- Regional Coordinator

NJDOT- Office of Government & Community Relations

1035 Parkway Avenue

Trenton, NJ 08625

Phone number: 609.963.2798

Email: sengbey.patience@dot.nj.gov